

Florida Department of Environmental Protection



Division of Environmental Assessment
and Restoration

Estimated Nitrogen Loading to the Upper Floridan Aquifer: Nitrogen Source Inventory and Loading Tool for Weeki Wachee Spring

*Kirstin Eller and Brian Katz
Ground Water Management Section*

June 14, 2016

Kirstin.Eller@dep.state.fl.us
Brian.Katz@dep.state.fl.us
Richard.W.Hicks@dep.state.fl.us



Nitrogen Source Inventory and Loading Tool

- Estimate N loading to ground water with BMAP areas
- Identify sources for which reductions in N loading could achieve restoration of impaired waters
- Customize for individual spring basins
- Inventories have been completed for Wakulla, Silver, Rainbow, Kings Bay, Jackson Blue Springs BMAP areas




2

Weeki Wachee Spring and Weeki Wachee River were verified by FDEP as impaired by nutrients and were included on the verified list of impaired waters for the Withlacoochee Basin that was adopted by Secretarial Order in May 2009. There are multiple sources of nitrogen that have contributed to the water-quality impairment of Weeki Wachee and Weeki Wachee River.

The Nitrogen Source Inventory and Loading Tool (NSILT) was developed to identify and quantify the major sources contributing nitrogen to ground water in the Weeki Wachee BMAP area. The NSILT is a GIS- and spreadsheet-based tool that provides spatial estimates of the relative contribution of nitrogen from various sources, and takes into consideration the transport pathways and processes affecting the various forms of nitrogen as they move from the land surface through soil and geologic strata into the Floridan aquifer. This analysis is part of the new Florida Springs and Aquifer Protection Act.



BMAP Boundary




3

The area that is included in the Basin Management Action Plan for the Coastal Springs of Pasco and Hernando Counties is larger than the Weeki Wachee contributing area. For this analysis, we are focusing only on the Weeki Wachee contributing area. The Aripeka contributing area will be assessed separately later this year.



Weeki Wachee Contributing Area



This map was prepared on 05/20/16 by FDEP Ground Water Management Section. For display purposes only. For more information: K.Eller (850)245-8652.

There are multiple springs included in the Weeki Wachee Springs contributing area including Little Spring, Jenkins Spring, Hospital Spring, Mud Spring, Salt Spring and Wilderness Spring. All of these springs discharge from the same aquifer and have similar nutrient reduction needs.



Estimating Nitrogen Loads to Ground Water

Steps:


1. Estimate the inputs of nitrogen to the land surface from the source inventory information (**best available**).
2. Apply attenuation factors based on the various environmental processes that could transform the various forms of nitrogen in the subsurface (such as denitrification, nitrification of ammonia, uptake by plants, mineralization of organic nitrogen).
3. Apply areal weighting factors that are based on the rate of recharge to ground water to estimate nitrogen loads to ground water.
4. Fine-tune estimates after getting feedback from stakeholders.



Our multiple step approach begins with estimating the nitrogen input to the land surface from various sources within the Weeki Wachee BMAP boundary. Next, we estimate the environment's ability to uptake and utilize this nitrogen which is called attenuation. Then, we evaluate the degree of recharge throughout the BMAP boundary. This will naturally vary with the geological conditions and influences the quantity of water reaching the aquifer. We apply a weighted recharge factor to account for this recharge variation. The final step to this process is reaching out to stakeholder groups and seeking their expertise to help us understand the different nitrogen sources and management practices.



Nitrogen Cycle and Nitrogen Attenuation



Processes that control the transformation of N in soils and the subsurface.


The wide ranges reflect variable soil conditions, fertilizer material, livestock, crop types, etc.,
ALL AFFECT LEACHING OF N TO GROUND WATER

6

This is a cartoon describing our process. The nitrogen source categories are listed in the top; each with its own input into the environment. The processes listed in the brown bar describe the attenuation or how the environment is able to process and take up nitrogen. For our estimates, we are interested in the bar labeled "Leaching of Non-attenuated N". This is the nitrogen which is not utilized by the environment and has the potential to reach ground water.



Ground Water Recharge Areas




- ◇ Quantify the rate of recharge to the UFA within the WW contributing area
 - ◇ High Recharge: >10 in/yr
 - ◇ Medium Recharge: 3-10 in/yr
 - ◇ Low Recharge: 0-3 in/yr
- ◇ Rates are weighted to estimate loading potential for each source category

Here is the Weeki Wachee contributing area and associated recharge rates to the Upper Floridan Aquifer. As you can see, the majority of the area has high recharge with over 10 inches of water every year infiltrating to the ground water.



Weeki Wachee Land Use



- ◇ Majority of N inputs occur within agricultural and urban land areas
- ◇ These represent 55% of the land use within the BMAP area

This chart illustrates the various land uses within the Weeki Wachee contributing area. The majority of nitrogen sources will enter the environment within an urban or agricultural landscape or within 55% of the BMAP boundary.




Atmospheric Deposition

◇ TDEP model

- ◇ U.S. EPA method to estimate spatially continuous atmospheric deposition
- ◇ Nationwide total deposition model for N and S
- ◇ Estimated deposition based on monitoring stations and modeled atmospheric concentrations
- ◇ Model year is an average from 2011 to 2013
- ◇ Average TN deposition
 - ◇ Range 3.7-8.8 lb-N/ac/yr

Recharge Area	Input to Land Surface (lb-N)
Low	24,093
Medium	197,719
High	923,127




9

For atmospheric deposition, we rely on a nationwide model developed by EPA called the TDEP. This approach relies on data from monitoring stations as well as other atmospheric models. At the recommendation of the developers, the model results used included data from 2011 to 2013.



Wastewater Treatment Facilities

- ◊ 13 permitted facilities
 - ◊ 2 with discharge ≥ 0.1 MGD
 - ◊ 4 with discharge < 0.1 & ≥ 0.01 MGD
- ◊ TN effluent concentrations as reported to DEP
- ◊ NO_3 used to project TN data, if necessary



- ◊ Effluent data separated based on treatment type
 - ◊ RIBs, Absorption Fields
 - ◊ Sprayfields
 - ◊ Reuse

Treatment Type	Recharge Area	Input to Land Surface (lb-N)
RIB	Medium	389
Sprayfield		213
RIB	High	39,776
Sprayfield		10
Reuse		53,873


Wastewater treatment facilities are required to report various nutrient and flow data as part of their permits for operating. We use this data to estimate the input from these facilities to the land surface using the total nitrogen in the effluent as well as the actual flow rate from each facility. If nitrate data is available, but not total nitrogen, then the nitrate concentrations are projected to total nitrogen based on a 2009 DEP study. The estimated input to the land surface is separated based on the type of effluent treatment: rapid infiltration basins (RIBs), absorption fields, sprayfield or reuse.



Septic Tanks

- ◊ DOH model relies on tax parcel data and sewer service areas
- ◊ Accuracy of this data was verified using an aerial analysis
- ◊ Calculate # of people relying on septic tanks
 - ◊ Hernando County = 2.08 people per household
 - ◊ Pasco County = 2.07 people per household
 - ◊ 34,201 tanks in BMAP boundary
- ◊ Average annual input to septic tank = 9.012 lb-N/person (US EPA)

Recharge Area	Input to Land Surface (lb-N)
Low	2,552
Medium	20,332
High	617,033




The number of septic tanks within the contributing area is estimated based on a DOH 2009 model. The effective population in each county is estimated based on the number of people per occupied household (2010 US Census) and the amount of time an average person will spend at home in a given year (US Labor Statistics). This data allows us to calculate the number of people using septic tanks and apply an annual N factor per person to estimate the input to land surface.



Nitrogen Input: Livestock Waste

- ◇ Literature review provided information on
 - ◇ Common livestock animals in Florida
 - ◇ Animal waste factors
- ◇ 2012 Census of Agriculture (CoA)
 - ◇ US Dept of Agriculture
 - ◇ Every 5 years
 - ◇ # of livestock (categorized by animal)
 - ◇ Full county data ONLY



Animal	Daily Waste Factor (lb-N/day)
Beef Cattle	0.337
Dairy Cow	0.977
Broiler Chickens	0.159
Goats	0.035
Hogs	0.190
Sheep	0.198
Turkey	0.006
Horses	.273





12

Full county livestock populations are taken from the 2012 Census of Agriculture. We use land use percentages to take the full county data and use it to estimate the populations within the contributing boundary. The full county data are listed in the table along with the daily waste factors associated with each animal.



Land use Percentages: Livestock

- ◊ Pastures
 - ◊ Improved
 - ◊ Unimproved
 - ◊ Woodland
- ◊ Feeding Operations
 - ◊ Cattle
 - ◊ Poultry
 - ◊ Dairies
- ◊ Specialty Farms
 - ◊ Horse Farms



- To calculate the land use percentages, we look at the land use for the entire county. Listed here are the land use categories which are likely to contain livestock animals.
- The land use data for Hernando County is used as an example. The same calculations were made for Pasco County.
- The total livestock land use acreage is calculated for the entire county.
- The same calculation is made for just the BMAP boundary which indicates that 66% of all the livestock lands in Hernando County are also in the BMAP boundary.
- 40% of the Hernando County livestock lands are within the High recharge areas of the BMAP boundary.
- 26% of the Hernando County livestock lands are within the Medium recharge areas of the BMAP boundary.
- There is not a percentage for the low recharge areas because they all fall within Pasco County.



Livestock Waste

Animal	Estimated BMAP population
Beef Cattle*	6,270
Dairy Cows	539
Horses	2,367
Broiler Chickens	659
Goats	1,380
Hogs	298
Sheep	334
Turkey	31

*Beef Cattle population estimated based on a stocking rate vetted by local agricultural producers of 8 ac per cow

Recharge Area	Input to Land Surface (lb-N)
Low	543,411
Medium	1,483,111
High	1,890,911




14

Those land use percentages are then applied to the total county livestock populations reported in the 2012 Census of Agriculture. This estimates the number of animals within the WW contributing area. Daily waste factors (see slide 12) are used to estimate the amount of nitrogen contributing to the BMAP boundary from these livestock populations. The largest nitrogen contribution is associated with cattle.



Farm Fertilizers



This map was prepared on 08/11/14 by FDEP Ground Water Management Section. For display purposes only. For more information: K.Eller (850)245-8652.

Recharge Area	Input to Land Surface (lb-N)
Low	65,327
Medium	503,752
High	881,498

- ◇ Property appraiser land use data was compiled
- ◇ Each county was evaluated individually
- ◇ Land areas for specific crops were estimated
- ◇ Application rates based on IFAS recommendations and farmer feedback
 - ◇ 17-60 lb-N/ac: Pastures
 - ◇ 80 lb-N/ac: Hay, Watermelons, Berries
 - ◇ 90 lb-N/ac: Ornamentals
 - ◇ 150 lb-N/ac: Orchards


15

The land area for each crop is estimated based on property appraiser data as well as personal communication with the agricultural property appraiser. The application rates listed are based on the IFAS recommended rates as well as discussions which took place with agricultural producers throughout the state.



Urban Turfgrass Fertilizers

- ◊ Acreage likely to receive fertilizer estimated from PA data and property values
- ◊ Annual Application Rates based on SWFWMD study
 - ◊ 68% fertilized by owners
 - ◊ 15% @ 0.5 lb-N/1000 sq ft
 - ◊ 59% @ 0.8 lb-N/1000 sq ft
 - ◊ 27% @ 1 lb-N/1000 sq ft
 - ◊ 2.98 times year
 - ◊ 32% fertilized by lawn service
 - ◊ 0.5 lb-N/1000 sq ft
 - ◊ 2 times a year
- ◊ Impervious surfaces estimated based on zoning laws



Recharge Area	Input to Land Surface (lb-N)
Low	15,177
Medium	254,447
High	2,097,868


16

Urban fertilizers includes fertilizer application for residential purposes, businesses, parks, etc. Golf course and sporting facility fertilizer use is estimated separately. Land areas were estimated based on property appraiser data. The amount of impervious and therefore not fertilized land area was calculated using county zoning laws. The probability of fertilization was also taken into account based on property value which has been identified as an indicator of fertilizer use by socioeconomic studies. The remaining pervious surfaces are assumed to be fertilized at various rates which are derived from multiple SWFWMD studies completed in the Citrus county area.



Sports Turfgrass Fertilizers

- ◇ Sports fields
 - ◇ Acreage estimates from aerial analysis of PA landuse data
 - ◇ Application rates based on lawn service company estimates
- ◇ Golf Courses
 - ◇ Acreage estimated through PA landuse data
 - ◇ Application rates based on data provided by golf courses
 - ◇ Annual application rate = 2.6 lb-N/1,000 sq ft



Recharge Area	Input to Land Surface (lb-N)
Low	---
Medium	2,769
High	202,243


17

Sports turfgrass includes sporting facilities like baseball and football fields as well as golf courses. The acreage associated with sporting facilities was estimated based on an evaluation of PA landuses likely to contain these fields including schools, parks and recreational areas. The nitrogen application rate was estimated using the data for lawn service company fertilization practices (Urban Turfgrass Fertilizers slide).

Golf courses were estimated based on the acreage assessed by the PA offices. The fertilizer application rate is based on voluntary surveys completed by some of the golf course superintendents in the contributing area. For those golf courses which did not complete a survey, an average application rate of 3.24 lb-N/1,000 sq ft was estimated; an average application rate. In total, the average application rate for the contributing area is 2.6 lb-N/1,000 sq ft



Biochemical Attenuation Factors



- ◊ Represent the percentage of N removed and therefore not available for leaching to groundwater
- ◊ Based on factors used in similar past studies and found in relevant literature


Loading Category	N Attenuation Factor	N Leaching
Atmospheric Deposition	90%	10%
Septic Systems	60%	40%
WWTF-RIB	25%	75%
WWTF-Sprayfield	60%	40%
WWTF-Reuse	75%	25%
Urban Turfgrass Fertilizers	80%	20%
Sports Turfgrass Fertilizers	80%	20%
Farm Fertilizers	80%	20%
Livestock	90%	10%

After all the nitrogen input to the land surface has been estimated, attenuation factors are applied. This table lists the attenuation factors for each nitrogen source. These factors are the result of an extensive literature and peer review. There is a range for all these factors however, these values represent an average attenuation expected given Florida's environmental conditions. These factors represent the amount of nitrogen which is taken up by the environment. For example, the 90% attenuation for atmospheric deposition means that 90% of all the nitrogen from atmospheric deposition that falls onto the land surface will be taken up by the environment and will not leach into ground water. This leaves 10% of the atmospheric nitrogen with the potential of leaching to the aquifer.



Hydrogeological Attenuation Factors Based on Recharge to UFA

- Recharge factors are used to estimate the percentage of the non-attenuated nitrogen expected to reach the aquifer in a year




19

Our final step in estimating N loads to ground water is to apply the recharge factor based on where each contributing source is located within the BMAP boundary. In the high recharge area, we estimate that 90% of all the non-attenuated nitrogen will reach the aquifer, 50% in the medium recharge and 10% in the low recharge.



Estimated Annual Average Loading to Ground Water

Weeki Wachee




988,548 lb-N/yr

20

Here are the current results illustrating the relative contribution of nitrogen from various nitrogen sources within the BMAP boundary. These results represent an estimation of the nitrogen currently entering the aquifer within the Weeki Wachee BMAP boundary and not an estimation of the concentrations exiting the springs. The spring discharge is a mixture of water which has entered the aquifer over a varied amount of time.



Estimated Annual Average Loading to Ground Water



21

The majority of the nitrogen is entering ground water within the high recharge areas. Within just the high recharge, urban turfgrass fertilizer is the largest contributor followed by septic systems. Livestock waste and farm fertilizers are the largest contributors within the medium and low recharge areas.




Weeki Wachee Spring Discharge of Nitrogen

◇ Current

- ◇ Discharge = 185.6 ft³/sec
- ◇ TN = 0.96 mg/L
- ◇ Load = 349,411 lb-N/yr

◇ TMDL

- ◇ Using current discharge
- ◇ TN = 0.28 mg/L
- ◇ Load = 102,178 lb-N/yr



22

This plot illustrates that the estimated nitrogen load to groundwater is higher than what is currently discharging from the spring. This may indicate that we are over-estimating the amount of nitrogen entering the subsurface within the Weeki Wachee contributing area. Or, there could be considerable nitrogen storage in the subsurface, which may enter the aquifer slowly over time.

The most important thing to note is the nitrogen load discharging from the spring is higher than the target TMDL. The management practices implemented with the BMAP over time will help to improve the overall water quality of Weeki Wachee Spring. We are continually refining the NSILT methodology and results as new data become available. In the future, we hope to receive more detailed information about nitrogen application practices including those associated with urban fertilizer usage and storm water runoff to catchments.



QUESTIONS??



Division of Environmental Assessment and Restoration
Ground Water Management Section

Brian.Katz@dep.state.fl.us
Kirstin.Eller@dep.state.fl.us
Richard.W.Hicks@dep.state.fl.us