

4 Protective Bollards 2 ft X 2 ft Concrete Pad with SJRWMD Survey Marker Static GWL : _____ ft bls Grout Type: <u>PORTLAND CEMENT</u> Quantity: <u>11</u> Grout Type: <u>PORTLAND CEMENT</u> Quantity: <u>3</u> Seal Type: <u>BENTONITE CHIPS</u> Quantity: <u>1</u> Filter Pack Type: <u>20/30</u> Quantity: <u>10 BAGS 50 lb</u> PVC Bottom Cap (6 inches)		3.0' -ft Stick-up Locking Compression Cap with Hinged Lid and 6" X 5' Steel Protective Outer Casing LSD (est. @ ~ _____ ft NGVD) Casing Type: <u>PVC</u> Diameter: <u>8"</u> Depth: <u>16'</u> ft Casing Type: <u>4" PVC</u> Diameter: <u>4"</u> Depth: <u>20.0'</u> ft Tag Holeplug @ <u>16.0'</u> ft bls Tag Sand @ <u>18.0'</u> ft bls Screen Type: <u>PVC</u> Slot Size: <u>.010</u> Interval: <u>10-ft.</u> Total Depth @ <u>30.0'</u> ft bls 8" inch dia. bore
Not to Scale		
Site: <u>CANAVERAL MARSH</u> Driller: <u>TONY HUDSON</u> Method: <u>ROTARY</u> Date Completed: <u>11-5-09</u>		SJRWMD Well ID: <u>BR-2162</u>