

Steel Protective Outer Casing with
locking 6 x 6-inch hinged lid

LSD (est. @ ~ 120-ft NGVD)

Stick-up
2.90-ft

4- Protective Bollards

2-ft x 2-ft Cement Pad
SJRWMD Survey Marker

Static WL: 67.7-ft bls
70-ft bls

8-inch dia. SCH 40 PVC Casing (70-ft)
12-inch dia. bore
Portland Cement (20-bags)

76-ft bls

4-inch dia. SCH 40 PVC Casing (80-ft)
8-inch dia. bore
Portland Cement (11-bags)

78-ft bls
80-ft bls

Holeplug (1-bag)

83-ft bls

20/30 silica sand filter pack (5-bags)

85-ft bls

Gravel filter pack (3-bags)

90-ft bls

4-inch dia. 0.010 slot SCH 40 PVC
well screen (10-ft)

20/30 silica sand filter pack (5-bags)

8 -inch dia. bore

Drilled Mud Rotary
Developed with air and submersible
pump.

Not to Scale

Site: Lake Gem
Driller: Huss Drilling, Inc.
Well Completed: April 1, 2010

SJRWMD

Figure 2. Intermediate Monitor Well OR1109