

Steel Protective Outer Casing with
locking 6 x 6-inch hinged lid

LSD (est. @ ~ 120-ft NGVD)

Stick-up
2.95-ft

2- Protective Bollards

2-ft x 2-ft Cement Pad
SJRWMD Survey Marker

Static WL: 68.4 -ft bls
70-ft bls

8-inch dia. SCH 40 PVC Casing (70-ft)
12-inch dia. bore
Portland Cement (28-bgs)

80-ft bls
130-ft bls

4-inch dia. SCH 40 PVC Casing (130-ft)
8-inch dia. bore
Portland Cement (44-bgs)

Holeplug (13-bags)(130-80-ft)

Open Hole (50-ft)

Drilled Mud Rotary
Developed with air and submersible
pump.

180-ft bls

4 -inch dia. bore

Not to Scale

Site: Lake Gem
Driller: Huss Drilling, Inc.
Well Completed: March 31, 2010

SJRWMD

Figure 3. Floridan Monitor Well OR1110