

Steel Protective Outer Casing with
locking 6x6 inch hinged lid

Stick-up
2.7-ft

2 x 2 ft Cement Pad with 2 Protective
Bollards

Static WL: 7.43-ft bls

4-inch dia. SCH 40 PVC Casing (50-ft)

Portland Cement (11-bgs)

46-ft bls

Bentonite Seal (1-bg)

48-ft bls

50-ft bls

4-inch dia. 0.010 SCH 40 PVC screen

20/30 Sand Filter Pack (7-bags)

60-ft bls

PVC Bottom Cap (inches)

8-inch dia. bore

Not to Scale

Site:	Scoggins Lake Rd
Drilled:	Mud Rotary
Developed:	Submersible Pump
Rate:	37.5 gpm
Pumping GWL:	24.29-ft bls
Specific Capacity:	2.22 gpm/ft
Lat/Long:	291101.12/811005.89 WGS 84
Driller:	Huss Drilling, Inc.
Well Completed:	August 13, 2010

Field Water Quality

Specific Conductivity: 381.0 $\mu\text{S}/\text{cm}$

Chlorides: 11.0 mg/l

pH: Not recorded

SJR WMD

Figure. Monitor Well V-1188