

 FUTURE ASPHALT NOT PART OF THIS PROJECT
(CONTRACTOR SHALL INSTALL 6" COMPACTED LIMEROCK BASE TO THE EXTENTS
SHOWN AS PART OF THIS CONTRACT. ELEVATIONS SHOULD BE GRADED TO BE 2'
BELOW FINAL ROADWAY GRADES AS SHOWN IN THE SITE DRAINAGE PLANS.

- ← DIRECTION OF TRAFFIC FLOW

NOTE:

ALL STRIPING SHOWN IS FOR REFERENCE ONLY. STRIPPING TO BE COMPLETED IN THE FUTURE.

STRIPPING TO BE COMPLETED IN
CONTRACTOR SHALL USE BMP ALONG
CONSTRUCTION AREAS ABUTTING WETLAND LINE
TO LIMIT IMPACT TO WETLANDS. (TYPICAL)

EXISTING ROAD TO BE CUT FOR UTILITIES
INSTALLATION. ROAD TO BE RESTORED
PER DETAIL ON SHEET C502.

CONTRACTOR TO LIMIT TREE/VEGETATION
REMOVAL TO THE MINIMUM NEEDED IN
ORDER TO INSTALL UTILITIES, CAMPSITES,
CAMPSITES PADS, AND GRADING.
CONTRACTOR TO TAKE CARE TO SAVE AS
MUCH VEGETATION/TREE AS POSSIBLE (TYP.).

PHASE I

PHASE II

6' WIDE GRAVEL ACCESS WITH
FENCE ON BOTH SIDES.

THIS SITE TO BE CONSTRUCTION
AS PART OF PHASE II.

PROPOSED LIMITS
OF FUTURE ROAD
ASPHALT (NOT PART
OF THIS PROJECT)

CONTRACTOR SHALL USE BMP ALONG
CONSTRUCTION AREAS ABUTTING WETLAND LINE
TO LIMIT IMPACT TO WETLANDS. (TYPICAL)

SITE BENCHMARK #4
TOP OF PK NAIL & DISK
WITH "BM" LB #7143
ELEV = 2.94 (NAVD '88)
N: 416084.52
E: 1576883.46

EM

REFER TO MEP PLANS FOR ALL
ELECTRIC PEDESTALS (TYP.)

PLANS FOR ALL
DESTALS (TYP.)

EXISTING ROAD TO BE CUT FOR
UTILITIES INSTALLATION. ROAD
TO BE RESTORED PER DETAIL
ON SHEET C502.

PROP.
CONCRETE
CAMPSITE (TYP.)

ADA CONNECTION
TO BH3 (SLOPE TO
NOT EXCEED 2%
CROSS SLOPE OR
5% RUNNING
SLOPE)

CONTRACTOR TO ADJUST OR RE-CONSTRUCT ADA RAMPS / STAIRS TO MEET CURRENT GRADING DESIGN AND ADA SLOPES.

UNLESS OTHERWISE NOTED, SAVE AND PROTECT EXISTING DUMP STATION, UTILITIES, SIDEWALK, WOOD DECKS/RAMPS, BATH HOUSE, AND ETC.

UNLESS OTHER WISE
NOTED, SAVE AND
PROTECT EXISTING
DUMP STATION,
UTILITIES, SIDEWALK,
WOOD DECKS/RAMPS
BATH HOUSE, AND ETC.



~~CROSSWALK
PER FDOT. (SLOPE TO NOT
EXCEED 2% CROSS SLOPE
OR 5 % RUNNING SLOPE)~~

EXISTING ROAD TO BE CUT FOR UTILITIES INSTALLATION. ROAD
TO BE RESTORED PER DETAIL ON SHEET C502.

TWO CONCRETE PADS FOR DUMPSTER FOR BH3 & BH
DUMPSTER PAD TO OF 8" CONCRETE (4,000 PSI) OVER
4" COMPACTED BASE MATERIAL.

CONTRACTOR TO LIMIT TREE/VEGETATION REMOVAL TO THE MINIMUM NEEDED IN ORDER TO INSTALL UTILITIES, CAMPSITES, CAMPSITES PADS, AND GRADING. CONTRACTOR TO TAKE CARE TO SAVE AS MUCH VEGETATION/TREE AS POSSIBLE (TYP.

NOTE: ALL EXISTING CAMPSITES AND CAMPSITES UTILITIES TO BE REMOVED FOR CONSTRUCTION OF NEW IMPROVEMENTS.



SHEET NO.	ST. ANDREWS STATE PARK										PROFESSIONAL REGISTRATION JASON LAMAR TOOLE, P.E. LICENSE NUMBER - 66531				DESIGNER : JCP	ISSUE DATE: 07-11-17	SUBMITTAL	DATE	REVISION	SYMBOL	DATE	REVISION	SYMBOL	DATE
	SHEET TITLE											DRAWN BY: JCP	COMP. FILE No.: F13605	(A)	(A)	(C)								
												REVIEWED BY: JLT	STATE PROJECT No.: 61109C	(A)	(A)	(C)								

*Department of Environmental Protection
Office of Operations
Bureau of Design and Construction
3300 Commonwealth Blvd., Tallahassee, FL 32399 (850) 425-2300*

	A Full Service A & E Firm		Offices In:
	Architects Engineers Environmental Landscape Architects Traffic/Transportation	M/E/P Planners Structural Surveyors	• Florida • Puerto Rico • Connecticut • Maryland • Texas
Consultant : www.cphcorp.com			

ST. ANDREWS STATE PARK

SHEET TITLE
EROSION CONTROL-DEMOLITION-SITE PLAN

PROJECT TITLE
CAMPGROUND RE-INVESTMENT

SHEET NO.

C102