



FLORIDA DEPARTMENT OF Environmental Protection

Marjory Stoneman Douglas Building
3900 Commonwealth Boulevard
Tallahassee, FL 32399

Ron DeSantis
Governor

Jeanette Nuñez
Lt. Governor

Shawn Hamilton
Secretary

November 29, 2023

NOTICE TO APPLICANTS ADDENDUM NO. THREE (3)

John Pennekamp Coral Reef State Park- Restroom Replacement DEP BID NO. BDC16-23/24

TO BIDDERS AND PLAN HOLDERS ON THE ABOVE REFERENCED PROJECT:
PLEASE NOTE CONTENTS HEREIN AND INCLUDE, SIGNED, WITH YOUR BID
SUBMISSION.

NOTICE

It will be required that this addendum be signed in acknowledgment of receipt and that it be included with your Bid when same is submitted to Macey Robinson, Contracts Specialist, Bureau of Design and Construction, 3800 Commonwealth Blvd., MS #520, Tallahassee, Florida, 32399-3000. Failure to do so may be grounds for rejection of the Bid.

Signature of Contractor and Date

The following statements supersede & supplement the corresponding items in the specifications & drawings:

- 1. Question:** Appendix E in the Geotech report specifications for the augercast piles paragraph 2.03 states that two test piles shall be installed, and static load tested by the Contractors as directed by the Geotech engineer. It also states to provide tension load test on the piles. Please clarify if the contractors must provide test piles since the title of the specification's states (not to be used for construction). This is confusing.

Answer: Test piles are not required.

- 2. Question:** The Note on Detail 1 "Piling and Column Section" on sheet S102 states "All reinforcement shall be galvanized" Does this only applies to the columns and piles or to the entire rebar for the entire structure (i.e., elevated slab, masonry walls and tie beams)?

Answer: Please refer to the Structural Plan Notes:

Masonry section, item #7

7. All reinforcing steel to be hot dipped galvanized grade 60 per astm a615, reinforcing bars shall be placed in the middle of the cells and tied or otherwise securely supported at the top and bottom to ensure the bar does not move during grouting. Minimum lap at all splices or dowels shall be per tension lap splice schedule, unless otherwise noted on the drawings.

Cast in place concrete section, item #3

Reinforcing steel: all reinforcing steel shall be hot dipped galvanized for foundation slabs, footings, cmu walls & tie-beams, astm a1094, astm a615, grade 60, fy = 60,000 psi.

3. **Question:** According to the specification the bridge at the campground can only support 30 tons. Unfortunately, the small drill rig for the augercast piles weight 32.5 tons. Will the Owner let this drill rig drive over the bridge? If not, will the type of pile change to a drilled shaft?

Answer: Please clarify what bridge is rated for 30 tons. Records indicate that the wooden bridge into the Far Beach area was rated for 66 tons based on meeting minutes from the design kick-off meeting. The campground is not near the proposed restroom project area.



4. **Question:** Please provide the model and size for the hand dryers?

Answer: P101 calls for NOVA 1-0830, Automatic, Surface Wall Mounted ADA Hand Dryer Brushed White Enamel on Die Cast Aluminum, 220V, 7A, 1700W.

In all other respects, the contract documents of which this is an Addendum, and attachments relative thereto, shall remain in full force and effect.