



Florida Department of Environmental Protection

Update on Wekiva Septic Tank Research Activities


June 15, 2017





Typical Septic System

-typical gravity system





Key Activities

- Homeowner septic tank study
 - Homeowner meeting (March 2015)
 - Screening and selection of 11 study sites (June 2015)
 - Site instrumentation (July-August 2015)
 - Monitoring period, bi-monthly sampling (September 2015-October 2016)
- Experimental drainfield
 - Installation of experimental drainfield (August 2016)
 - Monthly monitoring of experimental drainfield (ongoing)



Wekiva Homeowner Study Objectives

The results of study helps us better understand:


- Attenuation and leaching of nitrogen from existing septic systems into the soil and ground water
- Other sources of nitrogen in residential areas
- Conditions that may influence nitrogen attenuation local to this area
- Influence of septic tank pumping on treatment



Information on Study Sites

Site ID	City	No. residents	Drainfield repair/replacement history	Maintenance info	Fertilizer use	Soil
A	Sorrento	2	infiltrators (original)	pumped regularly	yes, self applied	Candler fine sand
B	Apopka	3	infiltrators (2009)	pumped in 2013	yes, self applied	Candler fine sand
C	Apopka	3	infiltrators (2010)	septic tank pumped in 2013	yes, self applied	Candler fine sand
D	Apopka	2	pipe in gravel (original)	not pumped out lately	yes, commercial service	Candler fine sand
E	Apopka	2	pipe in gravel (1989)	not pumped	yard mostly mulched beds	Candler fine sand
F	Apopka	4	infiltrators (2010)	pumped in 2014	not lately	Candler fine sand
G	Apopka	3	pipe in gravel (original)	pumped in 2014	yard mostly mulched beds	Candler fine sand
H	Apopka	2	pipe in gravel (original)	not pumped	yes, commercial service	Candler fine sand
I	Longwood	1-2	infiltrators (1989)	pumped in 2015	yes, commercial service	Urban land
J	Longwood	2	mounded pipe in gravel bed	pumped regularly	yes, commercial service	Urban land
K	Apopka	2	pipe in gravel (original)	pumped in 2015	yard mostly mulched beds	Candler fine sand

11 Study Site Locations





Types of drainfields in study





Figure 4 - Schematic of a Sand Mound System



Scope

- Install and sample lysimeters to monitor soil pore water below drainfields and at background locations
- Install risers for septic tank effluent monitoring
- Install and sample monitoring wells at two locations
- Attempt to collect data on water use to estimate loading



Soil Pore Water Monitoring

Site	Lysimeters Installed	Total Depth (ft below land surface)	Location
A	AL1S-AL4S	5	Drainfield
	AL5S	5	Background
	AL2D	10	Drainfield adjacent to AL2S
B	BL1S-BL4S	5	Drainfield
	BL5S	5	Background
	BL3D	10	Drainfield, adjacent to BL3S
	BL3E	15	Drainfield, adjacent to BL3S
C	CL1S-CL3S	5	Drainfield
	CL4S	5	Background
D	DL1S-DL2S	5	Drainfield
	DL3S	5	Background
E	EL1S-EL3S	5	Drainfield
	EL4S	5	Background
F	FL1S-FL3S	5	Drainfield
	FL4S	5	Background
	FL2D	10	Drainfield, adjacent to FL2S
G	GL1S-GL2S	5	Drainfield
	GL3S	5	Background
	GL1D	10	Drainfield, adjacent to GL1S
	GL1E	15	Drainfield, adjacent to GL1S
H	HL1S-HL2S	5	Drainfield
	HL3S	5	Background
I	IL1S-IL3S	5	Drainfield
	IL4S	5	Background
J	JL1S-JL3S	5	Drainfield
	JL4S	5	Background
K	KL1S-KL4S	5	Drainfield
	KL5S	5	Background



Lysimeter Installation



Wekiwa Spring






Septic Tank Effluent Sampling

Septic tank effluent samples collected bimonthly at 8 sites.
Results in mg/L.

Site	Average Total Nitrogen	Average Chloride	TN/Chloride Ratio	Average Total Phosphorus
A	61	32	1.91	7.8
B	93	43	2.16	9.3
C	101	63	1.60	12
E	57	47	1.21	6.8
F	57	45	1.27	6.8
G	75	42	1.79	7.5
I	140	87	1.61	16
J	93	74	1.26	9.3
All Sites	85	54	1.57	9.4



Source: Ext. DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community

Wekiva Septic Study Site: C




0 5 10 20 30 Feet


L = Lysimeter
S = Shallow
D = Deep
E = Very Deep
MW = Monitoring Well

✕ Septic Tanks
● Sampling Site
▨ Drainfield



Map prepared 4/12/2017 by the Division of Environmental Assessment and Restoration. This map is not for legal decision making purposes. For more information or copies, contact David.Huggins@dep.state.fl.us





Source: Esri, DeLorme, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community

Wekiva Septic Study Site: E




0 5 10 20 30 Feet


Map prepared: 4/12/2017 by the Division of Environmental Assessment and Restoration. This map is not for legal decision making purposes. For more information or copies, contact David.Huggins@dep.state.fl.us

L = Lysimeter
S = Shallow
D = Deep
E = Very Deep
MW = Monitoring Well

Septic Tanks
Sampling Site
Drainfield







Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community




Wekiva Septic Study Site: K




Map prepared 4/12/2017 by the Division of Environmental Assessment and Restoration. This map is not for legal decision making purposes. For more information or copies, contact David.Huggins@dep.state.fl.us

L = Lysimeter
S = Shallow
D = Deep
E = Very Deep
MW = Monitoring Well







Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, AeroGRID, IGN, and the GIS User Community

Wekiva Septic Study Site: D







Map prepared: 4/12/2017 by the Division of Environmental Assessment and Restoration. This map is not for legal decision making purposes. For more information or copies, contact David.Huggins@dep.state.fl.us

L = Lysimeter
S = Shallow
D = Deep
E = Very Deep
MW = Monitoring Well

✕ Septic Tanks
● Sampling Site
▨ Drainfield







Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community

Wekiva Septic Study Site: J




0 25 50 100 150 Feet

Map prepared 4/12/2017 by the Division of Environmental Assessment and Restoration. This map is not for legal decision making purposes. For more information or copies, contact David.Huggins@dep.state.fl.us




L = Lysimeter
S = Shallow
D = Deep
E = Very Deep
MW = Monitoring Well


✕ Septic Tanks
● Sampling Site
▨ Drainfield

















**Wekiva Septic Study
Site: F**




Map prepared: 4/12/2017 by the Division of Environmental Assessment and Restoration. This map is not for legal decision making purposes. For more information or copies, contact David Huggins@dep.state.fl.us

L = Lysimeter
S = Shallow
D = Deep
E = Very Deep
MW = Monitoring Well









Summary Findings for Lysimeter Samples

Site	Max TN	Min TN	Avg TN	Max Chloride	Min Chloride	Avg Chloride	Max TP	Min TP	Avg TP
A	132	0.96	37	81	0.04	26	3.6	0.034	0.89
B	254	1.5	49	180	1.6	33	3.6	0.008	0.32
C	67	0.83	19	67	6.5	30	1.2	0.033	0.38
D	22	1.3	6.0	28	2.7	13	2.1	0.053	1.2
E	103	0.74	22	94	2.9	37	1.9	0.11	0.77
F	112	7	42	56	1.3	18	6.1	0.047	1.8
G	152	2.2	49	2600	5.8	234	7.9	0.04	1.8
H	10	1.5	6.3	92	1.9	24	0.12	0.021	0.07
I	69	0.6	8.5	120	3.9	21	2.3	0.048	0.80
J	56	0.56	4.0	96	2.2	24	0.12	0.015	0.038
K	192	0.43	31	260	1.3	55	8.2	0.32	3.0



Information about drainfield-related N attenuation

Results from some of the sites where TN was mostly from drainfields during some portion of the monitoring period are summarized below.

- At Site E, 39 % of nitrogen was reduced with 10% due to dilution.
- At Site G, 42 to 46 % of nitrogen was reduced in shallow and deep lysimeters with no dilution.
- At Site J where there is a shallow water table, 35 % of the nitrogen was reduced in a shallow well with no dilution.
- At Site K, 44 % of nitrogen was reduced with no dilution.

Using data from multiple sites, it appears that attenuation of N by means other than dilution is about 40 % (based on assumed TN/CI relationship)



Soil Attenuation Modeling



SSSA Onsite
Wastewater Conference
April 7-8, 2014

The Florida Onsite Sewage
Nitrogen Reduction Strategies
(FOSNRS) Project


FOSNRS 6: STUMOD-FL - A Tool for Predicting Fate and Transport of Nitrogen in Soil Treatment Units in Florida

April 7, 2014

Mengistu Geza¹, Kathryn S Lowe¹, Cliff Tonsberg¹, John McCray¹ and Eberhard Roeder²

¹Civil and Environmental Engineering, Colorado School of Mines, Golden, CO




²Division of Disease Control and Health Protection Bureau of Environmental Health,
Florida Department of Health, Tallahassee, FL





Septic Tank Effluent and Influence of Pumping

- Midway through the study, 4 septic tanks were pumped. Others left as control.
- Septic tanks at sites A, B, E and G were pumped in March 2016, between February and April monitoring events





General statistics for all sites

†


Site	TN Before	TN After	% Chg	Chloride Before	Chloride After	% Chg	TP Before	TP After	% Chg
A ¹	55	65	+18	30	34	+13	6	9	+5
B ¹	97	90	-7	43	42	-2	9	9	0
C	101	100	-1	63	60	-5	12	11	-8
E ¹	45	65	+44	46	48	+4	5	8	+60
F	56	65	+18	45	48	+7	6	8	+33
G ¹	79	73	-8	43	42	-2	8	7	-13
I	128	149	+16	83	90	+8	15	17	+13
J	77	106	+38	71	76	+7	5	12	+140

Notes: ¹- septic tank pumped in March 2016. Other sites are controls.

□



TN Trends after pumping





Alternative Drainfield Research

Construction Summary: Assessment of the Nitrogen Removal and Viability of a Reactive Layer with Liner under a Conventional Septic System Drainfield

Division of Environmental Assessment and Restoration

Florida Department of Environmental Protection

August 2016


2600 Blair Stone Road, MS 3575
Tallahassee, Florida 32399-2400
www.dep.state.fl.us









Wood mulch and liner extend
3-5' beyond edge of drainfield





LEGEND

- shallow suction lysimeter
- deep suction lysimeter
- horizontal well point
- riser for effluent monitoring
- monitoring well
- piezometer


















TN results through March

Shallow Lysimeters - Total Nitrogen mg/L



Deep Lysimeters - Total Nitrogen mg/L



Deep lysimeter average 65-75 % lower than STE



Conclusions

- Soil pore water monitoring at typical sites has provided some interesting information:
 - Drainfield and shallow soil, associated TN reduction of 40-45%
 - Fertilizer influence intermittent but significance
 - Working on calibration of soil attenuation model, then final report (anticipate July 2017)
- Septic tank before and after pumpout results
 - No clear trends were noticed to indicate that pumpout improves treatment by the tanks
- Experimental lined drainfield
 - Results are consistent, maybe a little better, than original site
 - Continued monitoring
 - Promise that these types of drainfield enhancements can be applied



Questions?

