

Florida Department of Environmental Protection - DWH Restoration Projects
 Project Title: W-3 Recreation Loss: Boardwalks and Dune Crossovers
 Montigo Avenue Beach Access Improvements
 County, Municipality, or Agency: Walton County
 DATE: September 17, 2012

Cost Items	Cost Estimate
Planning	
Contracts	
Feasibility	
Engineering & Design ¹	11,000
Planning Administration ²	
[other]	
Planning Subtotal	11,000.00
Construction	
Contracts ³	135,166
Construction Administration	
[other]	
Construction Subtotal	135,166
Monitoring	
Contracts	7,000
Monitoring Administration	
[other]	
Monitoring Subtotal	7,000
Project Cost	
TOTAL	153,166

¹ includes data collection, design, permitting, landrights, bid documentation prep, etc. necessary to bring a project to contract readiness

² Administration costs for each section include overhead and indirect costs to conduct that portion of project implementation

³ Should include construction cost detail such as projected unit costs for each construction item, mob/demob, plantings, and any corrective actions (if applicable)

Montigo Ave Parking Lot Improvements

NO.	ITEMS	QUANTITY	UNITS	UNIT PRICE	TOTAL PRICE
1	1.5' SP-9.5 (165#/sy) Asphalt	137	TN	\$105.00	\$14,385.00
2	8" Limerock Base (LBR 100 Min.)	1516	SY	\$16.00	\$24,256.00
3	12" Subgrade (LBR 40 Min.)	1516	SY	\$3.00	\$4,548.00
4	Install A-2000 18" Pipe	190	LF	\$38.00	\$7,220.00
5	Install FDOT Index 232 Type C Inlet	4	EA	\$2,200.00	\$8,800.00
6	Install FDOT Index 272 M.E.S.	2	EA	\$800.00	\$1,600.00
7	FDOT Type F Modified Curb and Gutter	460	LF	\$16.00	\$7,360.00
8	4" Thick Concrete Sidewalk	247	SY	\$37.00	\$9,139.00
9	Earthwork	1	LS	\$12,000.00	\$12,000.00
10	Bicycle parking rack	1	LS	\$800.00	\$800.00
11	Thermoplastic pavement markings and signage as shown on plans	1	LS	\$7,000.00	\$7,000.00
12	Clearing and Grubbing	1	LS	\$2,200.00	\$2,200.00
13	Sodding (5' perimeter and all of SW pond)	500	SY	\$2.50	\$1,250.00
14	Timber Dune Walkover (6' wide)	90	LF	\$200.00	\$18,000.00
15	Dune planting and restoration	2000	SF	\$0.96	\$1,920.00
16	Erosion Control- Including all silt fences, hay bales, etc., as required to contain runoff.	1	LS	\$1,200.00	\$1,200.00
17	Layout (Including all Required Surveying for alignment)	1	LS	\$1,200.00	\$1,200.00
18	Bonds (Maximum 5% of Bid)	1	LS	\$6,143.90	\$6,143.90
19	Mobilization (Maximum 5% of Bid)	1	LS	\$6,143.90	\$6,143.90
				Total =	\$135,165.80
Engineering to include survey design and permitting					\$18,000.00