



May 21, 2001

DEPARTMENT OF
ENVIRONMENTAL PROTECTION

MAY 29 2001

SITING COORDINATION

Mr. Hamilton Oven
Professional Administrator
Transmission Line Siting
2600 Blair Stone Road
Mail Stop 48
Tallahassee
FL 32399-2400

RE: Levee-Midway 500kV TLSA : Connections to Midway Substation

Buck
Dear ~~Mr. Oven~~:

Per our earlier conversation, this letter is to advise you of a minor adjustment we are making on a previously installed connection associated with the Levee-Midway 500 kV transmission line at our Midway Substation. As you will recall, this transmission line was permitted under the TLSA. Currently the Levee-Midway line comes up from the south, passes the substation equipment on the west, then loops around and connects into the substation from the north. We propose to disconnect one of the links of the transmission line from this northern bay and reconnect it into a bay on the south side of the substation. A sketch is enclosed to illustrate the old and new configurations. The re-routed section of line will be entirely located on FPL property and existing easements and no new right-of-way is required.

I would appreciate your written acknowledgement for the file that this rework will not require any further TLSA review.

Condition G-2 of the Certification requires that this line comply with the state standards for electric and magnetic fields. In compliance with this condition, an EMF submittal will be provided at least 90 days before construction of the re-routed line into the substation.

If you have any questions please give me a call at 561-691-7059.

Sincerely

Florette Braun

Florette Braun
Principal Environmental Specialist
Environmental Services

Copy

Jose Coto FPL
Carolyn Raepple HGSS

L-M TLSA Midway connect 5-01

LEVEE-MIDWAY TSLA
PRIMARY CORRIDOR

TO
POINSETT

BAY BAY BAY BAY
4N 3N 2N 1N

MIDWAY SUBSTATION
500 kV SECTION

BAY BAY BAY BAY
4S 3S 2S 1S

TO
CORBETT

EXISTING MARTIN-MIDWAY
(PERMITTED UNDER
LEVEE-MIDWAY TSLA)

MARTIN-MIDWAY
PROPOSED RELOCATION

TO
MARTIN



APPROVED

----- EXISTING TO BE REMOVED
----- PROPOSED NEW CONSTRUCTION

MIDWAY SUBSTATION
PROPOSED 500 kV
LINE ARRANGEMENT


DATE 5/10/01
SCALE NTS

SHEET OF

A-

DRAWN BY		DATE		REVISION		BATCH	COPI	APP
CHECKED								
CORRECT								

MIDWAY
SUBSTATION



EXISTING FPL
RIGHT-OF-WAY

FPL EASEMENT

